rigidianiya. TTDTT

#### CHAPTER IX

#### VE EXAMPLES

#### Introduction

This chapter contains examples of successful application of VE demonstrating the broad range of products and circumstances for applying VE effort.

#### I. TF 39 Engine Exhaust Nozzle Replacement


# SAN ANTONIO ALC VALUE ENGINEERING (VE) PROJECT

SUBJECT: TF 39 ENGINE EXHAUST NOZZLE REPLACEMENT

BEFORE: \$1,141,885.00/YRWAS COST TO OVERHAUL AND REPLACE ENGINE EXHAUST NOZZLES WHICH SEEMED EXCESSIVE . A VE TEAM ANALYZED THE PROBLEM AND INITIATED TESTING ON NOZZLES PREVIOUSLY REMOVED FOR OUT-OF-TOLERANCE DENTS AND BULGES.

AFTER: STUDY AND ENGINE TESTING SHOWED ONLY 15% OF ENGINE THRUST GOES THROUGH THIS NOZZLE AND DAMAGE TOLERANCES COULD BE OPENED FROM .020''" TO .50" WITH NO SIGNIFICANT EFFECT. THIS REDUCED FIELD REMOVAL BY 50% AND ALLOWED FIELD REPAIR OF MOST OF THE UNITS; THEREFORE , MOST OF THE EXPENSIVE DEPOT REPAIR WITH ASSOCIATED SHIPPING COSTS WAS ELIMINATED . PREVIOUSLY CONDEMNED NOZZLES COULD BE REWORKED AND RETURNED TO SERVICE.

SAVINGS: \$1,038,568.00 FIRST YEAR.



#### II. C-5B Aircraft Landing Gear Brakes

An example of a VE study done on the C-5B aircraft landing gear brakes for the U.S. Air Force is shown below. The VE study centered on the substitution of material, which realized a net savings to the Government of \$7,800,000.




#### **MLG WHEEL BRAKES**

#### BEFORE:

٠ .

C-5B AIRCRAFT LANDING BRAKES CONSTRUCTED OF BERYLLIUM MATERIAL

- 1. MATERIAL SERIOUS HEALTH HAZARD DURING REFURBISHMENT
- 2. HIGH COST MATERIAL
- 3. SPECIAL CLOTHING REQUIRED DURING HANDLING/REFURBISHMENT
- 4. 750 LANDINGS



#### AFTER:

C-5B AIRCRAFT LANDING GEAR BRAKES CONSTRUCTED OF SPECIALLY TREATED HARDENED CARBON MATERIAL

- 1. NO HEALTH HAZARD DURING REFURBISHMENT
- 2. LOWER MATERIAL COST
- 3. NO SPECIAL CLOTHING REQUIRED
- 4. SIGNIFICANTLY MORE LANDINGS

NET OVERALL SAVINGS TO THE GOVERNMENT -\$7,800,000

#### III. AN/TYC-39 Automatic Message Switch




The U.S. Army Communications and Electronics Command received and approved - a VECP from the contractor to reduce life-cycle costs of the Dessage switch for those applications not requiring a 50-line capability. This was achieved by replacing the existing dual shelter message switch with a single Dessage switch, as shown below. While providing adequate communications capability, the single shelter message switch resulted in savings in equipment acquisition costs, training, maintenance, and operational needs.



# VALUE ENGINEERING PROGRAM USACECOM AN/TYC-39 MESSAGE SWITCH

**BEFORE** 







**AFTER** 

- 50 LINE DOUBLE SHELTER MESSAGE SWITCH
- TWO 5 TON TRUCKS
- 60 KW GENERATOR
- TWO TRUCK OPERATORS

- MESSAGE SWITCH
- ONE 5 TON TRUCK
- 30 KW GENERATOR
- ONE TRUCK OPERATOR
- REDUCED MAINTENANCE
- FEWER SPARES
- REDUCED FUEL CONSUMPTION


COMMUNICATIONS SYSTEMS DIVISION GTE PRODUCTS CORPORATION NEEDHAM HEIGHTS, MA VECP **TOTAL** CONTRACT SAVINGS: \$1,994,000 ROI - **12:1** 

#### IV. Use of Commercial Alternator In Lieu of Military Alternator

The U.S. Army Tank-Automotive Command conducted an in-house VE study which researched the possibility of using two commercial 100 AMP alternators in lieu of 180 AMP military-type alternators without sacrificing quality performance. The military type alternator design features an assembly of two units, a generator and rectifier-voltage regulator. The commercial diode-rectified generator (often called alternator) features a simple one-unit design and is less costly to produce. By replacing the military-type alternator with the commercial unit, improved performance and cost reduction was attained. The first year's net savings was \$11,896,163. The implementation cost was \$10,000, or a return on investment of 1190 to 1.

### US ARMY TANK-AUTOMOTIVE COMMAND

# USING SIMPLER COMPONENTS BEFORE VE




FIRST YEAR SAVINGS: '11.9 Million

٧.

The US Army Armament Materiel Readiness Command received and approved a VECP on its M14 Aiming Post Light. For the previous design a labor-intensive □ ethod of fabrication was seriously limiting the production rate. In addition the old design resulted in operational and maintenance problems. The heavy draw of the incandescent bulb required daily battery replacement and its nonwaterproof design led to frequent failure due to galvanic corrosion. As shown below, the new design permitted higher production rates, extended the battery life to 1,000 hours, and was waterproof. The annual savings achieved through this VECP was \$222,497.

## IMMCOVECP's4028-16/17-M14 AIMING POST LIGHT




CHARACTERISTIC	OLD STYLE	VALUE Engineered	IMPROVEMENT
COST	\$18.52	\$9.25   5	50%
BATTERY LIFE	8-12 HRS	10000 HRS RS	9,900%
WEIGHT	19 Oz	7 Oz	63%
MIN OPERATING TEMP	ABOUT 0°F	" BELOW-30°F	SIGNIFICANIT
WATERPROOF	NO	YES	SIGNIFICANT
MATERIALS	WARTIME CRITICAL	COWWON -	SIGNIFICANT
LIGHT COLOR CHANGE	CHANGE LENSES	FLIP SWITCH	SEIGNATICANT
SHAOE	<ul> <li>REQUIRED</li> </ul>	NOT REQUIRED	SECONFICANT
PRODUCTION RATE	LIMITED	VERY HIGH	SIGNIFICANT

AVG ANNUAL GOVT SAVINGS - S222.500 RETURN ON INVESTMENT -23'1

#### VI. M60 Tank Seat Brackets

# US ARMY DEPOT SYSTEM COMMAND Anniston Army Depot MODIFYING SEAT BRACKETS

#### BEFORE **VE**




- New seat support brackets required for M60 tank conversion from AI to A3
- New procurement required
- New brac!rets: \$196.53 each



#### AFTER VE

- ortglnai Al modified to A3 configuration
- New procurement eliminated
- Modified brackets
   12 80 each



FIRST YEAR SAVINGS: '120,000

#### VII. MK 82 Bomb Skins

......

The bomb skin (shell) of the MK .82 Bomb is used during peacetime training. When available supplies were exhausted, a new procurement of the bomb skins was planned. The bomb skins were available from the production contractor at a cost of \$430 ● ach. The U.S. Army Armament Materiel Readiness Command conducted a Value Engineering study on the bomb skin and the training requirement. The study determined that old MK 82 bomb skins from items being demilitarized could be refurbished and used for training at a cost of \$70.93 each. This resulted in a first-year savings of \$3.5 million and a return on investment of 6 to 1.

# US ARMY ARMAMENT MATERIEL READINESS COMMAND

### REFURBISHING MK 82 BOMB SKINS BEFORE VE,

nal 3m


 ElonItr skins needed for additional training requirements

New procurement needed

Newtraining bomb skins '430 each

NEW BOMB SKIN
FROM PRODUCTION CONTRACTOR

### AFTERVE



- in-house refurbishment of available demilitarized bomb skins
- Cost savingsper bomb skm 35907

FIRST YEAR SAVINGS: \$3.5 Million RETURN ON INVESTMENT: 6 to 1


In the directorate for maintenance at the New Cumberland Army Depot, there were no rework procedures for certain aircraft components that have nicks, pitting, corrosion, or scratches. These items were scrapped and sold for mixed metal at approximately \$0.02 per pound. An in-house VE study waar conducted, and the Selection Process was proposed and approved. This process is a completely mobile selective metal depositing deposition system for resizing, restoring and repairing worn or damaged metal parts without the need far costly disassembly, complicated masking, Indian not not periods of down time. The build-up areas will be equal to or have I better metallurgical quality than the existing base metal. There was an Innual gross savings of over \$5,000,000, with an implementation cost of approximately \$34,000 at the New Cumberland Army Depot. This proposal was recommended to be adopted ArmyWide. If it is implemented ArmyWide the Government should realize an annual savings in excess of \$100,000,000.




### US ARMY DEPOT SYSTEM COMMAND

New **Cumberland** Army Depot RECLAIMING **CH47** VERTICAL SHAFTS

#### BEFORE VE



#### AFTER YE



FIRST YEAR SAVINGS: '7.5 Million RETURN ON INVESTMENT: 11 to 1


1 17 17 17

The U.S. Army Mobility Equipment Research and Development Center designed and developed on air compressor for filling air tanks for Army scuba divers. The MIL-SPEC compressor was designed to user requirements. The estimated procurement cost of this compressor was \$40,000 each. A Value Engineering study was performed on the design specifications, and the user requirements. The changes to the specifications and user requirements resulting from the study established the "actual" performance requirements. Although commercial compressors could not meet the original specifications and requirements, the "actual" performance requirements could be met by some commercial compressors. Commercial compressors were-procured at a cost of \$16,000 each. A first-year savings of \$879,000 and return on investment of 88 to 1.


# US ARMY MOBILITY EQUIPMENT RESEARCH AND DEVELOPMENT COMMAND

# SUBSTITUTION FOR MIL-SPEC COMPRESSOR BEFORE VE

- Rigid air flow rate and pressure specifications
- Suitable commercial compressors not available
- MI L-SPEC compressor Cost: '40,000 each



#### **AFTER VE**




- Military s pacifications challenged and changed
- Some commercial compressors now suitable and safe under new specifications
- Commercial compressor Cost: '16.000 each


FIRST YEAR SAVINGS: '879,000 RETURN ON INVESTMENT: 88 to 1

Project as designed called for complete removal and replacement of all existing taxiway and apron materials. The contractor's proposal recommended removing the existing ashpalt pavement with a rota mill machine which grinds the material into pebble size granules. Then the recycled material is reused as base course material in lieu of purchasing and hauling in new base material.

# AIRFIELD TAXIWAY & APRON



### AS DESIGNED





MILL EXISTING PAVEMENT AND REUSE FOR NEW BASE COURSE.

## **ALTERNATE**

**SAVINGS** - \$88,684

The original design called for a specialized roof construction of bulb tees, cementations deck, rigid insulation and wood nailers. The contractor's proposal recommended a more conventional and less costly roof construction sequence of steel decking and poured in place zonolite insulation fill. The proposal was evaluated and accepted,





SAVINGS -\$43,000

W




The project required reworking the existing trickling filter by ramming the existing stone bed (media) and replacing it with a very high cost PVC media. The contractor upon investigation of the existing trickling filter and stone base, recommended removing, cleaning and reinstalling the existing stone media in lieu of installing the very high cost PVC substitute media. The proposal was evaluated and approved.

# SEWAGE COLLECTION & TREATMENT


#### **BEFORE:**

REMOVE STONE MEDIA & INSTALL PVC MEDIA.



### **AFTER:**

REUSE EXISTING STONE MEDIA.




**SAVINGS** - \$338,600



# DAY & ZIMMERMAN, INC. VECP KS-4012-154

PLASTIC EXPULSION CHARGE ASSEMBLY FOR M483A1-155MM PROJECTILE



BAG ASSEMBLY

\$4.52

PLASTIC CUP ASSEMBLY


\$1.13

**UNIT SAVINGS \$3.39** 

3 YEAR SAVINGS FOR THE US ARMY \$4,680,000

# VECP 0668

### REDESIGN OF FUEL PYLONS



#### **AFTER VECP:**



PARTS REQUIRED FUR ASSEMBLY = 24

TOTAL PARTS REDUCED = 38

TOTAL SAVINGS= \$20.8 MILLION





GENERAL DYNAMICS Fort Worth Division

# **VECP 0875**

#### COMPUTER GENERATED TECHNICAL MANUALS

#### . PRIOR TO VECP:



MANUALL Y GENERATED
5 TRANSACTIONS BEFORE DELIVERY TO CUSTOMER

#### **AFTER VECP:**

ENGINEERING — LOGISTICS — CUSTOMERI

COMPUTER GENERATED (REQUIRED REVISION TO MILITARY SPECIFICATIONS)

1 TRANSACTION BEFORE DEL/VERY TO CUSTOMER

TASKS ELIMINATED:

REPRINTING (LOGISTICS)
REVIEW (ENGINEERING)

TOTAL SAVINGS: \$990,000





#### XVI . Men's Dress Shoes

A VE study conducted at Army's Natick Research and Development Laboratories focused on substitution of new materials for the leather in men's dress shoes. The substitution of synthetic rubber soles for the traditional leather soles resulted in a savings of \$3 per pair of shoes. This savings translated into a \$2,811,996 reduction in the cost of procuring the first year's requirement of these shoes for the Military Services.

#### XVII. Automated Pay Data Requirements

At the Sacramento Air Logistics Center (SM-ALC), a review was made of the efforts utilized in collecting civilian pay related information by Resource Cost/Center Code. This procedure is needed to calculate the Civilian Fringe Benefit Factor, as required by OMB Circular A-76. Approximately 800 man-hours were required to collect and calculate the required information. An additional 30 hours was required to type the results in a prescribed format. A value analysis of the above methods and procedures resulted in a program designed for a particular minicomputer. This program eliminates manual data collecting and calculations, while printing the output in the prescribed format. Although this project only saved \$10,118 per year at SM-ALC, it was recommended for Air Forcewide consideration.

XVIII. Drone Formation Control System (DFCS) To Control Multiple Ground Targets

In order for the White Sands Missile Range (WSMR) to support the Assault Breaker Project, a system was required which could present as many as ten ground targets (tanks) in a remotely controlled configuration. The criteria the targets had to meet were that they should be separated by 50 to 100 meters, that their position be controlled with an accuracy of + 10 meters or better, and that they travel a roadway as narrow as 15 meters. Since WSMR's capability to control ground targets was limited to manual remote-control of two vehicles, it appeared a new tracking and control system would be required. This would have meant a developmental effort and a rather lengthy, costly contract.

A WSMR employee proposed modifying an existing system (i.e., Drone Formation Control System (DFCS)), which was originally designed to control aerial targets, in lieu of acquiring a new control system. The modified system provides the capability to track and control as many as 15 tank targets within the constraints described above. Twelve tanks are instrumented to provide two back-up (spare) units. The cost of acquiring a new system was conservatively estimated to be \$2,811,000. The cost of modifying the DFCS was \$285,000. This resulted in savings of \$2,526,000.